KOLAR DIVISION.

Approximate estimate of quantities relating to the work of improving the Sri Venkataramanaswamy's Temple at Thalakayalakonda, Sidlaghatta Taluk.

Serial No.	Items of work	Unit	Dismantling old dilapidated mantaps	Reconstructing the old mukhadwaram with two new side rooms using old materials	Constructing a Vahanasala and a room attached to it	Constructing a Kalyana Mantapam	Constructing a Bhojanasala with kitchen and store room	Constructing Yagasala and Alwar's temple	Compound wall	Grand Total
			Quantity	Quantity	Quantity	Quantity	Quantity	Quantity	Quantity	Quantities
1	Dismantling old mantaps walls and roof, etc., and removing the stuff to some distance and using the same for bringing up the low portions of the Compound.	Sqr.	37·03	....	....	....	....	....	....	37·03
2	Dismantling old compound walls and removing the stone to some distance from the premises.	100 C. ft.	47·10	....	....	....	....	....	....	47.10
3	Clearing site of boulders, etc., on the north-east corner of the compound and widening the car road on the north-west corner.	..	Lumpsum	....	....	....	....	....	....	Lumpsum
4	Benching rock as per detailed estimate ..	..	....	Lumpsum	....	....	....	....	....	Do
5	Erecting mukhadwaram as per detailed estimate with old materials.	..	....	Lumpsum	....	....	....	....	....	Do
6	Burnt stone in chunam	100 C. ft.	....	2·21	14·12	7·58	32·01	21·18	....	77·10
7	Burnt brick in mortar	,,	....	4·49	1·19	....	4·69	....	....	10·37
8	Burnt stone slabs 6" thick dressed including chunam pointing.	100 S. ft.	....	3·14	4·74	2·19	14·47	6·40	....	30·94
9	Burnt stone slabs 4½" to 6" thick dressed including chunam pointing.	,,	....	....	6·25	5·04	26·88	6·25	....	44·42
10	Burnt stone slabs 9" thick 1' broad dressed for beams including chunam pointing.	,,	....	0·66	1·00	0·72	3·99	1·45	....	7·82
11	Roofing slabs using old available slabs including chunam pointing.	,,	....	2·86	....	....	....	262	....	5·48
12	Roofing with brick concrete including plastering.	Sqr.	....	6·92	....	....	....	....	....	6·92
13	Concrete with brick in chunam including plastering.	,,	....	....	10·15	8·65	45·92	13·75	....	78·47
14	Parapets bricks in chunam 9" x 2' x 0" with coping and plastering complete.	R. ft.	....	116	88	62	266	120	....	652
15	Plastering with chunam	Sqr.	....	17·88	3·59	....	13·82	....	....	35·29
16	Pointing with chunam	,,	....	2·38	16·02	4·65	19·08	20·98	28·60	91·71
17	White-washing	,,	....	17·88	3·59	....	....	....	....	21·47
18	Teakwood doors with 1½" thick batten shutters with locking arrangements, etc., and painting complete.	S. ft.	....	36	76	....	54	36	....	202

19	Teakwood windows with batten shutter, iron bars, etc., including painting.	S. ft.	....	18	18	....	52	5	....		141
20	Providing locks, iron bars, wood pegs in walls and iron rings in roofs for hanging lights, etc	..	....	Lumpsum	Lumpsum	Lumpsum	Lumpsum	Lumpsum	....		Lumpsum
21	Earthenware rain water spouts for the roof.	No.	...	8	7	8	22	10	....		55
22	Lamp post with lanterns	,,	....	3	1	1	2	1	....		8
23	Junglewood gate for the mukhadwaram	S. ft.	....	48	....	....	....	....	....		48
24	Earthwork	100 C. ft.	....	....	3·98	3·65	18·77	3·11	6·71		36·22
25	Burnt stone in mud using new stones ..	,,	..	....	....	....	....	....	28·35		28 35
26	Do using old available stones.	,,	....	....	....	....	....	....	28·35		28·35
27	Coping with burnt stone jelly and mortar	R. ft.	....	....	....	....	....	....	2·26		226
28	Gate pillars	..	....	....	....	....	....	....	Lumpsum		Lumpsum
29	Flat iron gate	S. ft.	....	....	....	....	....	....	36		36
30	Cut stone pillars 9" square	C ft.	....	....	....	17	....	17	....		34
31	Burnt stone in mud ..	100 C. ft.	....	....	....	....	12·72	....	....		12 72
32	Providing a cistern as per details ..	..	....	....	....	....	Lumpsum	...	....		Lumpsum
33	Providing mortar and pestle stones ..	No.	....	....	....	....	2	....	....		2
34	Do skylights one in each room ..	,,	....	....	....	....	2	1	....		3

N. ANANDALWAR,
Executive Engineer.